

# Contents

---

<b>About the Author</b>		<b>xi</b>
<b>Introduction</b>		<b>xiii</b>
<b>Chapter 1</b>	<b>Identifying the Work</b>	<b>1</b>
	Identifying the Work	2
	Reviewing the Maintenance Backlog	3
	Identifying Preliminary Work	6
	Risk Management	16
	Risk Identification	16
	Risk Quantification	17
	Risk Response Development	18
	Risk Response Control	19
	Defining and Limiting the Scope	19
	Defining the Constraints of the Shutdown	19
	Prioritizing the Proposed Work	20
	Preliminary Estimates of Proposed Work	21
	Determining Contract Work	24
	Determining Internal Labor Demands	25
	Job Input Cut-Off Date	25
	Prioritizing Last Minute Requests	25
	Summary	26
<b>Chapter 2</b>	<b>Planning the Work</b>	<b>29</b>
	Planning the Shutdown	29
	The Shutdown Organization	30
	Assigning Responsibility	32
	Parts, Material, and Equipment	32
	Shipping and Delivery	34
	Planning Thought Process	39
	Example of a Turnaround Planning Sheet	43
	Applying the Planning Thought Process to Large Jobs	46
	Example of Planning a Large Job	51

	Estimating Tips	54
	Determining Elapsed Time and Job Staffing	56
	Including Time Required by Operations	57
	Work Packages	58
	Contracts for Services	59
	Types of Contracts	59
	Contract Revisions	61
	The Bidding Process	61
	Bidding Requirements	62
	Standard Forms of Construction Contracts	63
	General Provisions of a Construction Contract	63
	Technical Specifications	69
	Reference Standards	71
	Summary	71
<b>Chapter 3</b>	<b>Scheduling the Work</b>	<b>73</b>
	Critical Path Method (CPM)	73
	Logic Network Conventions	74
	Preparing a Logic Network	76
	Finding the Critical Path	76
	Interfering and Free Float	79
	Load Leveling	81
	Project Duration versus Project Cost	86
	Program Evaluation and Review-Technique (PERT)	88
	The Monte Carlo Method	92
	Project Management Software	96
	Choosing the Right Program	97
	Sorting and Communicating Information	99
	Breakdown Structures	100
	Summary	101
<b>Chapter 4</b>	<b>Executing the Project</b>	<b>105</b>
	Shutdown Safety	106
	OSHA Requirements	106
	Developing Daily Schedules	107

	Updating Job Status	110
	Reporting Project Status	111
	Tracking Project Costs	111
	Summary	114
<b>Chapter 5</b>	<b>Reporting and Documenting the Shutdown Activity</b>	<b>117</b>
	Project Review Meeting	117
	Project File	119
	Final Report	119
	Sample Shutdown Report	120
	Safety	121
	Discussion of Major Shutdown Jobs	122
	Comments and Recommendations	126
	Summary	128
<b>Appendix A</b>	<b>Boiler Shutdown Example</b>	<b>131</b>
	Boiler History	132
	The Shutdown	134
	Identifying the Work	134
	Building the Work List	137
<b>Appendix B</b>	<b>Identifying Electrical Work to Be Performed During a Shutdown</b>	<b>145</b>
	Electrical Shutdown Checklist	145
	Months and Weeks Prior to the Shutdown	145
	During the Shutdown	155
<b>Appendix C</b>	<b>Machinery Inspection Prior to and During a Shutdown</b>	<b>163</b>
	Bearing Data	163
	Shaft Alignment Standards	165
	Run-Out Measurements	167
	Alignment Data Conventions and Checks	168
	The Definition of a Line	168
	Off-Zero Alignment	170
	Gear Drive Inspection Standards	172
	Gear Tooth Nomenclature	172

**x Contents**

Gear Maintenance	173
Gear Drive Backlash	174
Gear Failure Analysis	175
V-Belt Drives	178
Causes of Belt Slip	179
Incorrect Tension	179
Sheave Wear and Damage	180
Alignment	180
Belt Tensioning	181
Pumps and Mechanical Seals	182
System Curves	183
Pump Characteristic Curves	185
Combined System and Pump Curves	186
Pump Affinity Laws	187
Understanding Cavitation	190
Determining Pump Condition	191
Centrifugal Pump Repair	191
Mechanical Seals	199
Fans	203
Fan Laws	203
Fan Performance Curves	205
<b>Glossary</b>	<b>213</b>
<b>Index</b>	<b>219</b>